BANGALORE DISTRICT.

Notice, dated 1st November 1929.

Notice is hereby given that sealed tenders will be received in the Office of the President, District Board, Bangalore, St. Martha's Hospital Compound, Bangalore, up to 3 P.M., on Monday the 25th November 1929, for constructing a Third Class Travellers' Bungalow at Bannerghatta, Anekal Taluk.

2. An approximate estimate of quantities is given below. These quantities are not guaranteed.

3. The plans, detailed estimate, etc., may be seen in the Office of the President, District Board, Bangalore, between the hours of 12 NOON to 5 P.M on office days. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed and in no case the indefinite rate such as "so many percent less" will be accepted. The value of each item must be worked out to the rates tendered. Tenders not conforming to this rule will be rejected.

4. Each tender must be accompanied by a deposit of Rs. 350 (rupees three hundred and fifty) in cash or in currency notes, as earnest money, and be superscribed "Tender for constructing Third Class Travellers' Bungalow at Bannerghatta," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, Bangalore, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

6. The name of the successful tenderer, whose tender has been accepted, will be notified on the Notice Board in the District Board President's Office in due course. No enquiries regarding the acceptance or rejection of any tender will receive any attention.

7. Within eight days of the acceptance or rejection of the tender, the successful competitor will be required to execute the usual contract bond on stamped paper in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. For individual items of work under lump sum provision, rates tendered for similar items of works shall be paid, and for other items rates as per schedule of rates will be paid at the discretion of the President.

10. The Contractor shall be bound to execute any other item of work not provided in the estimate as per directions of the President District Board, and shall take such rates as provided in the schedule of rates.

11. The contractor shall complete the work by the end of April 1930. The President of the District Board will be competent to levy a fine not exceeding Rs. 50 for any infringement of the terms of the contract or for bad work or belated progress. If the contractor ceases or fails to abide by the terms of this notice or contract at any time during the currency thereof, he shall forfeit the security money to the District Board and also be bound to make good to the District Board any loss which may arise from such cessation or failure.

"FORM."

Approximate quantities of work for constructing a Third Class Travellers' Bungalow at Bannerghatta.

	Items of work	Approximate quantity	Unit.	Tender rate at which each work will be worked out
1.	Earthwork excavation	106	C.yd.	
2.	Burnt stone jelly concrete in mortar ...	730	C.ft.	
3.	Burnt stone in clay	2,610	"	
4.	Burnt brick in clay	3,367	"	
5.	Burnt brick in mortar	686	"	
6.	Pillars of re-inforced concrete (capitals and bases 9" diameter).	4	Each	
7.	Teak wood panelled doors complete (with chocolate painting).	199	S.ft.	
8.	Teak wood battened doors complete (with chocolate painting).	86	"	

Items of work	Approximate quantity	Unit	Tender rate at which each work will be worked out
9. Teakwood windows with panelled and glazed half shutters complete.	100	S.ft.	
10. Ventilators of teakwood with glazed shutters rectangular.	8¾	,,	
11. Ventilators of teak wood with glazed shutters circular.	62/7	,,	
12. Burnt stone slabs dressed by one line ...	523	,,	
13. Do roughly dressed ..	209	,,	
14. Stone wall plates	176	R.ft.	
15. Roofing with first class Bassel Mission tiles on teak wood reepers, etc., complete.	12·84	Sqr.	
16. Teak wood work wrought and put up with tarring.	43·62	C.ft.	
17. Ridge tiles set in mortar	68½	R.ft.	
18. Chunam border	112	,,	
19. Dormon long rolled steel Beams and Joists with lead lift and paint.	47·92	C.W.T.	
20. Jack arched terraced roof 9″ thick ..	11·83	Sqr.	
21. Burnt brick in mortar. Cornice work with plaster	210	R.ft.	
22. Plain parapet with burnt brick in mortar and chunam plaster.	208	,,	
23. Flooring with first class Bassel Mission tiles 9″ square on 3″ concrete bed with cement pointing.	3·36	Sqr.	
24. Kadapah slab flooring on 3″ concrete bed and cement pointing.	5·32	,,	
25. Concrete flooring with plaster	4·56	,,	
26. Sinks with spouts, etc.	Lump	sum	
27. Chunam plaster	76·18	Sqr.	
28. White Washing	55·27	,,	
29. Colour Washing	20·22	,,	
30. Galvanized iron sheet water spouts ..	16	Each	
31. Cement pointing	4·42	Sqr.	
32. Ventilating tiles (Bassel Mission)	6	Each	
33. Sirks and wovens, for kitchens and back rooms	Lump	sum	
34. Grinding stones	2	Each	
35. Gravel flooring	3 1/3	C.yd.	
36. Coping with burnt brick in mortar (including chunam plastering).	14½	R.ft.	
37. Tarring to walls of latrine	Lump	sum	
38. Boring hole in slab (9″ diameter)	1	Each	
39. Levelling ground, etc.	Lump	sum	
40. Stone year-board	1	Each	
41. Aligarh locks with duplicate keys 3″ ..	8	,,	
42. Teak wood windows with battened shutters complete.	50¾	Sq.ft.	

B. ABDUR RAHMON,
President, District Board.

TUMKUR DISTRICT.

Notification dated 30th October 1929.

It is hereby notified for the information of the general public that under section 17 of the Village Panchayet Regulation, Mr. Veerappa, is appointed as a member of Mallasandra Village Panchayet, Tumkur Taluk, in place of Mr. Surappa, who left the place for Madhugiri.

G. B. HEBLIKAR,
Deputy Commissioner.